MD 404 Dualization and Soil Cement

Presented by:

Bryan Smith, P.E.- Wagman Heavy Civil

d Valente - KCETechnologies

Roberto Barcena, P.E. - Wallace & Montgomery Assoc.





Agenda

- Project Overview Bryan Smith (Contractor, Wagman Heavy Civil)
 - Overview with Challenges and Keys to Project Success
 - Project Update
 - Drone Flyover
- Soil Cement QC Challenges Fred Valente (Owner, MD SHA)
 - Maryland Testing Criteria
 - Soil Cement Application
- Soil Cement and Pavement Design Roberto Barcena (Designer, Wallace Montgomery)
 - Pavement Design and ATC Overview
 - Soil Cement Design





MD 404 Project Overview

Bryan Smith, P.E. – Wagman Heavy Civil



404 Corridor Safety Constructors A Joint Venture of Wagman Heavy Civil, David A. Bramble, and Allan Myers



ADMINISTRATION


Project Details

- Owner: MD SHA
- Location: Queen Anne Area, Md.
- Scope of Work: Design-Build Project to Widen and Rehabilitate MD 404
- Contract Value: \$104,997,777.77
- Notice to Proceed: 6/7/16
- Substantial Completion: 11/21/17





404 Project Team






404 Corridor Safety Constructors A Joint Venture of Wagman Heavy Civil, David A. Bramble, and Allan Myers



STATE HIGHWAY ADMINISTRATION

Project Goals

- Schedule Fully open 4 lanes to traffic and substantially complete construction by Thanksgiving 2017
- Cost Deliver a cost efficient project at or below budget
- Safety Safe roadway with ZERO fatalities and serious injuries during and after construction
- Customer Satisfaction Receive 100% satisfaction from travelers along MD 404
- Mobility Minimize delay during construction and after construction







Traffic

- 23,000 vehicles per day
 Summer/18,000 typical
- 16% Trucks









Roadway Features

- 9 Miles of New WB Roadway
- 1 Bridge
- 31 Intersections
- 400,000 CY Cut, 325,000 CY Fill
- 22 Miles of Guardrail

- 101K LF of Silt Fence
- 220K TN of Asphalt
- 300K SY of GAB Base
- 274K SY of Soil Cement
- 1.5M LF of Pavement Marking




Westbound Eastbound









"Double Ditches"





Drainage Features

- SWM Facilities
 - SWM Swales = 84,350 LF (16 Miles)
 - 110 Grass Swales
 - 145 Wet Swales
 - 25 Bioswales
 - 6 Box Culverts
 - 20K LF of RCP Pipe
 - 140 Drainage Structures
 - 19 Major Pipe Road Crossings



404 Corridor Safety Constructors A Joint Venture of Wagman Heavy Civil, David A. Bramble, and Allan Myers





STATE HIGHWAY ADMINISTRATION

Environmental Challenges

- 17 WUS (Waters of the US) Stream Crossings
- Norwich Creek Stream Restrictions November 16 to June 30
- Extensive Environmental Quality Assurance Program and E&S Construction team
- 20 Acre Grading Units per Watershed



404 Corridor Safety Constructors A Joint Venture of Wagman Heavy Civil, David A. Bramble, and Allan Myers





STATE HIGHWAY ADMINISTRATION

Design Challenges

- 280+ Design Submissions
- Plan review by IDQA (Century), SHA PRD, MDE, HHD
- Included 29 Plan Packages with Multiple Redlines
 - 8 Mass Grading Packages
 - 4 Final Design Packages
 - 17 other packages for culvert installation, surcharge, etc.



996317D -	Salumitad Lo	e				Bennier sammer	ease one completer			Denotes 7 day advan	201
Lond Submitted Coddisation Tracking Log (Design Flows) Log nd : date						Denotes plansare currently under review				Denotes commente a	re :
						Denines Parisan	currently under the	looment		Denotes Reacy of Col	
	P10								IDQ4 Re	view Status	
famin. Nite	Patient Stagement	P1D Schnittal Habranca	Submitial Description	Purpose of Submittal	15Qa Subminal Date	s-tA Submittal Date	Sahrahmi Passer W SHA PW	IDQA Submittal (*estad to SFA *99)	Comments to 404 CSC / CSD	DQA Commonity (Posted to SRA PW)	
top to	2		Shound improvement Plan for Structure 3.3 Embournent	Roview survivage / wide drain design and werning deading of write	17 Oct 2015 27-Oct 2015	3 8-07 20.6 22-354-2006	3 %c= 2016 22-hm+2116	12 Col 2016 27-Cr6-2016	20 00, 2016	21 Ccl 2016	
ep it	1	Si Dedil ne Teshkin 601	Charlingers Dreinger(Groding Units Filterugh %) Factoger Statio62 (hreagh Statio89)	Mostly 3-The concernent construction, Mostly Role 13. and Modify N10 meter	4.0 0 2046	6 Crit 3066	60+216	4.0-27.06	1.5	S.R.	
×. 16	X/8/C		Frelininary and superbasign Natio	Borewo' Foundar and cape Planting Areas	11 Nov 2016	1 38 2015	: D., 2016	11 4 2016			
09-10	c	- 14	Shearing and Unamage (Seeding Units 11 through 12) For equil-She 104 through Ste. 174	However of Converts, 1950, Half Hoseni, and MOS Flans and Certails	16-04-2015	11-0/2-2010	21-04-0010	16-049-0811	-	-	
h+4:	3	J Dell ne Texision 805	Simpler Diversion and Temporary Studing at Kersy da- Group	Medit to have to graphy to accommodate USD more. Traditions a clear the generation onto	19-015-2016	21-025-0816	21-Cet-2015	18-Oct-2017	-	-	
93-11	¢	n	Free Possible years 1/50 Pbrs (50 10 Brough 17) Pre 406 Brough Str. 506	Bay over 1 fine Readway, SKIW, Brainege, 1/50, and MCTP and and Geralis	15 Nov 2016 14-Dec-2016 13-Jul 2017	24341-2017	-	15-Net-2018 14-5en-3/11	2-040-2015 21-040-2016	2-Dec-2116 21-Ger-2016	
03-16	¢	n	S primaske Management Design Teperkick, 19 The reliable Constant and States and States	Review SWM Design Report Salar review - Sta. 495 Homogra Sta. 537	15 Nex 2016 14-Date-2016 13 Jun 2017	24441-2012	-	15-N-0-2016 14-0we-2017	2-04-2011 21-04-2016	2-Dec-2116 21-Ger-2016	
9x 18		7 RedFre Revision at	Sitz Figure Ordinage (SU 6 through 8) Patriage B Next Similary III statized through SL and	Revise SWM and Rycass Often Grading to account for required SWM reducing:	15 Nov 2016 38 Nov 2016	2.0x 2012		15 Nov 2016	.f Kov 20.f	36 Nev 2536	
1-+C	e	ž.	Revenue 5-1 (Sta. 316) Final / PBB Submission	Bowneen Tran Cuber, E/SC, HZ (Theorem With Pierre and Details	21-95-2010	24-35-2010	39-4 ₀₈ -3716	21-956-2016	-	-	Γ
03.15	4		southerships (sin 100 ct) (S61 / fournables that	Box'ew of Celkort 1955, Foundations Plans, Botalis, and Boxet	24 Nov 2016 23 Jun 2017	13 Jan 2017 Dadi: Crilgi	18 ton 2017 (AuditOrity)	24 Nev 2016 35 Jan 2016	31 Key 2015	20 Key 2116	Γ
09-11	A.		Truction favoring facebooking on Appendix Stat. 1981 1996, ph. 200, 201	Basics of Bastechnical Recommendations for Extraorm and Screen Weill	2014/9-2017	27-841-2017	-		-	-	
n+-I:	<i>b</i>		Interim Starting Statechnical Report - Star Withourth S.a. 127	Brains of Schlechnics, Recommendations for Segment A Rough Stading (FRD Package 2.)	22-35-2014	6-5w-2017 (%d). C+1g)	5-Dev 2005 - (A. 43 Orde)	22-9%-2016	-	-	
JUL 10	1		httprin Grading Statedhrifti Report 191, 305 Trivelightstal 240	Review of Secteduries Recommendations for Segment A Rough Chadrug (1960 Package 24)	11 Nov 2016 6 Dec 2016	.3 Doc 2016 (2nd), Only)	13 Dec 2016 141010 (V)	11 924 2016	15 Koy 2015	16 fee: 2116	I
DJ. 16	4	а	9 na 3096 and 656 Paris (60-1 de ougr 6). Star 325 Prezade Ster 251	Now the of ${\bf F}$ has that ago and SWM Plans and Details	2 100/2016	1 8-07 2016	7 KUV 2015	/ Nor 2016			
16	4	"	Sinuctions 5-12 (Sinu SS) Final Endation Element / 200 Sistemation	Review in Flow Culture (1964, 0/30, - Iphinullos Report), and ISBN Plane and Details	5-EH-3016 14-De-2016	11-091-2016 20-091-2017	16-Deci2012 Penting	8-840-2016 14-1we-2017	12-Dec-2016	12-16-2017	I
ST 16	4	3 Belline Tealkinn 602	Roucture 5 8-Stal 1894001P30 / Agoncy Rovision	Revise MOS to Construct Wein Wall	22-De5-2016 3 Jan 2017	4 Ion 2017	4.021-2017	22 Do: 2016	30 Dec 2016	30 Dec 20.6	Ī
.50-16	e.		Structure 5-12 (Six, 55) Structure. The Electro	Here every of the verticities if to another one of the coefficients, and the commutation $\boldsymbol{\sigma}$	5 Dec 2015 Gdan-2017	2-ian-2117	-	5-56-5011	16-Eec-2016	14-0eo-2/110	
$\simeq 16$	e -		Ron chure 5 2 (Sca. 334) Ron chura. Rhai Rans	Review of Berlin soft Schuthard First Firms and Even s	16 Nix 2016	16 N.S 2016	16 %r= 2016	16 Nov 2016			ĺ
er 16	4		By a nichleen te Stor (2a 117, TML/ Foundation Hans	Review of DAS TSM Enumerations Prove Details, and Becom	30.151 2017	27.57 (2017					l
	2		Scient Wall (Sta 132 to Sta 155) TSM / Februarion This	Review of Screen Wall TS&L Foundations Plans, Defensy and Report	20 341 2017	2134 2017					ĺ
	¢	-11	Resentantier Konagement DeCyc Report (GL) Proceeding) - Sin, 142 through the IRB-	Review SUM Design Review Result ministry - Sux SUP Unsugn Stat Kitte	24 Nex 2010 5 Dec 2016 74Dec 2016	9 58 2015	9 Dec 2016	23, Kep-2716 3-Dec-2016	80 Ni~ 2016 N-200-2015	 R* Kerr 2017 G Decubit N 	
~ 16	100	Hiterine Josking (0)	Statisment Dranage (Stating Units (Chinage 17) For ogni Arn 154 mough (m. 474	Review or Sectord in SAVI Effortes and Section to or Construction Changes	15-New-2010 18 New 2010	22 9% 2015	27 No. 2746	15-hcs-2016 18 hcs 2016	3 Kov 20-7	17 Key 2716	Ι



Major Construction Challenges

- Aggressive Schedule- majority of construction completed in 12 months
- Sheer volume of work
- QA/QC- Soil Cement (Fred will cover)







Keys to Project Success

- Partnering
 - Bi-weekly Progress/Partnering Meetings ensured key player involvement and accountability
- Coordination
 - Weekly Joint Venture management and constructability meetings with DB Team
- Performance
 - All team members including SHA, Engineering Partners, JV Partners, and Subcontractors contributed to the delivery of the project





Project Status

- Notice to Proceed: 6/7/16
- Substantial Completion: 11/21/17
- Substantial Completion Bonus: \$5,000,000
- Contract Completion: 7/31/18







Drone Flyover

 September 2017, two months prior to substantial completion





404 Corridor Safety Constructors A Joint Venture of Wagman Heavy Civil, David A. Bramble, and Allan Myers



STATE HIGHWAY ADMINISTRATION

Fred Valente - KCI Technologies



404 Corridor Safety Constructors A Joint Venture of Wagman Heavy Civil, David A. Bramble, and Allan Myers



STATE HIGHWAY ADMINISTRATION

MD 404 Soil Cement Overview

- Pavement Section included 8" Soil Cement base
- Segments A&B used majority insitu materials
- Segment C used majority offsite borrow materials
- Lab Testing by DBT to establish required cement content based on varying materials







Keeping up with production:

- 225,000 SY of Soil Cement (7000 TNS of Cement)
- Peak Production of 2,200
 SY/day (multiple crews)
- Two testing sheds needed due to traffic and multiple soil cement operations







- Acceptance Criteria:
 - Maryland OMT requires unconfined compressive strength pills for acceptance
 - PCA does not recommend unconfined compressive strength tests based on molded specimens due to inconsistency of sampling and pill breaks
 - Solution to establish QC Plan, which assured proper mix and also perform additional proof rolling prior to GAB placement





- Acceptance Criteria:
 - 404 Team had Soil Cement Base Course NOT Cement Modified Subgrade
 - Cement Modified Subgrade is more typical application in Maryland with strength requirement of 300 PSI
 - Soil Cement Base Course not typical with 450 PSI strength
 - First big project in Maryland with this application requiring higher strength acceptance





- QC Work Plan provided additional verification tests:
 - 3rd Party provided additional Quality Assurance testing (moisture, compaction, cement content, etc.)
 - Key was to ensure product in field matched previously established Lab Verification Testing
 - Due to schedule and inconsistent testing, contractor went with 8% content although lower contents (5-6%) were approved in verification testing







• Compaction & Moisture:

- Proof rolling subgrade?
- Varying in-situ onsite materials used
- 1 Point Compaction test required to choose from family of curves
- Assure within 2% of optimum moisture content for proper compaction AND to verify cement is activated (multiple moisture checks)







- Compressive Strength Results:
 - Moisture vs Strength
 - Appears Moisture range did not affect strength
 - Overall pill breaks were very inconsistent

AP No: AC				MD 404 DUALIZA	TION				
Contract: AW8965170 MD 404 DUALIZATION FAP No: AC -NHPP-300-1(53)N									
DATE	PILL	SEG	CEMENT %	MOISTURE %	STATION	BREAK	AGE	BREAK RESULTS (PSI)	
05/04/17	2A	A	8	13.6	126+50	05/11/17	7	560	
05/04/17	2B	A	8	13.6	126+50	05/18/17	14	585	
05/04/17	2C	A	8	13.6	126+50	06/01/17	28		
05/08/17	3A	A	8	13.0	123+30	05/15/17	7	482	
05/08/17	3B	Α	8	13.0	123+30	05/22/17	14		
05/08/17	3C	A	8	13.0	123+30	06/05/17	28		
05/08/17	4A	A	8	12.9	121+90	05/15/17	7	263	
05/08/17	4B	A	8	12.9	121+90	05/22/17	14	413	
05/08/17	4C	A	8	12.9	121+90	06/05/17	28		
05/08/17	5A	A	8	13.1	120+00	05/15/17	7	422	
05/08/17	5B	A	8	13.1	120+00	05/22/17	14	631	
05/08/17	5C	А	8	13.1	120+00	06/05/17	28		
05/08/17	6A	A	8	8.9	118+50	05/15/17	7	319	
05/08/17	6B	A	8	8.9	118+50	05/22/17	14	181	
05/08/17	6C	A	8	8.9	118+50	06/05/17	28	201	
05/08/17	7A	A	8	12.0	117+30	05/15/17	7	730	
05/08/17	7B	A	8	12.0	117+30	05/22/17	14		
05/08/17	7C	A	8	12.0	117+30	06/05/17	28		
05/09/17	8A	A	8	10.5	115+70	05/16/17	7	274-27	
05/09/17	8B	A	8	10.5	115+70	05/23/17	14	774	
05/09/17	8C	A	8	10.5	115+70	05/25/17	28		
05/09/17	9A	A	8	11.0	110+80	05/16/17	7	100	
05/09/17	9B	A	8	11.0	110+80	05/16/17	14	395	
05/09/17	9C	A	8	11.0	110+80	06/06/17	28		





404 Corridor Safety Constructors A Joint Venture of Wagman Heavy Civil, David A. Bramble, and Allan Myers

STATE HIGHWAY

Soil Cement and Pavement Design

Roberto Barcena, P.E. - Wallace & Montgomery Assoc.





Pavement Design Requirements

- Pavement Sections for Highway Elements Provided in Request For Proposal (RFP)
- Design-Build Team able to develop Alternative Technical Concepts (ATCs)
 - Pavement Design Criteria:
 - AASHTO 93
 - MDOT SHA Pavement Design Guide
 - MDOT SHA Specifications for Construction and Materials





Soil Cement Definition

- Soil treated with a small proportion of Portland Cement with the objective of improving properties (American Concrete Institute)
- The amount of cement added to the soil is less than that required to produce a hardened mass, but is enough to improve the engineering properties of a soil example
 - Lowers Plasticity Index
 - Improves Bearing Capacity





Soil Cement Definition (in MDOT SHA Design)

- Soil Cement as part of:
 - Subgrade Improvement (Cement Modified Subgrade)
 - Part of the Pavement Sections (Soil Cement)





Soil Cement Mix Design

- MDOT SHA Specifications for Construction and Materials
- Portland Cement Association Soil Cement Lab Handbook
 - Submission of soil samples at least 45 days before placing soil cement
 - Identifying soil sources and sampling
 - Soil classification (A-1-a, A-1-b, A-3, A-2-4)
 - Determination of Optimum Moisture Content





Soil Cement Mix Design

- Determination of Cement Content
 - Trial of Cement Percentages (Seed value +2% ,-2% increments)
 - Strength: Unconfined Compressive Strength (UCS) : 450 psi (7 days cure)
- Durability
 - Freeze-Thaw Cycles (12 cycles, 14% loss maximum)
- Structural Layer Coefficient
 - SN = 0.20








Proposed Field Verification

• Light Weight Deflectometer (field) Vs UCS





MARYLAND DEPARTMEN OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION