Presented by:

Joe Bracken III



High Strength Bolts for Bridges

FHWA Supplemental Contract Specifications for Projects with AASHTO M164 (ASTM A325) High-Strength Bolts


November, 1989

Specification for Structural Joints Using ASTM A325 or A490 Bolts

Research Council on Structural Connections

AASHTO Industrial Fasteners Institute sylvania

A325 or A490 Bolt Dimensions



Topics

- Required Documentation
- Rotational Capacity Testing (PTM 427)
- Inspection Testing (PTM 429)
- Pre-Installation Verification Testing (Pub 408, Section 1050 and now <u>PTM 429</u>)
 - Turn-of-the-Nut
 - Calibrated Wrench
 - Impact Wrench
 - Manual Wrench



6

ASTM A563

4.8.1

Hot-dip and mechanically deposited zinc-coated Grade DH nuts shall be provided with an additional lubricant which shall be clean and dry to the touch.

www.dot.state.pa.us

ASTM F436

HARDENED WASHER

- •REQUIRED FOR RC TEST
- •REQUIRED IF OUTER FACE OF BOLTED PART HAS A SLOPE GREATER THAN 1:20
- •MINIMUM THICKNESS 5/16 INCH




Specification for Structural Joints Using ASTM F3125 Grades

> A325-A1852 or A490-A2880 **Bolts**

Research Council on Structural Connections

AASHTO Industrial Fasteners Institute sylvania

A1852 or A2880 Twist-Off Bolt Method



Tension Control (TC) Bolt

Snug bolt
Tighten to spline break
Verify tension is correct






 TC Bolts have their own built in torque control device and are installed without the use of torque controlled tools. The torque requirements of the bolts are achieved by engaging the bolt and nut with inner and outer sockets and drive with the electric shear wrench until the control groove shears of the spline. Strength Bolt Testing



- Advantages:
- 1. Proper bolt tension can be confirmed by the shear-off spline.
- 2. Visual Inspection (No torque gauges required.)
- 3. No special expertise required for installation.
- 4. Wrench adjustment not required
- 5. Installation can be achieved by one operator on one side of the structure.
- 6. Substantial reduction in installation noise.
- 7. Overall cost savings as a result of reduced to the of labor and time





Shipping and receipt inspection

Verify:


- Identity of contents
- Inclusion of MTR/MCTR and/or DCTR as appropriate




Assembly and Use Problems


Bolts and nuts in rusty or dirty condition





ATION





www.dot.state.pa.us




www.dot.state.pa.us

- Installation Procedures:
- 1. Place bolt thru hole in properly aligned joining members
- 2. Attach washer and snug tighten all assemblies in the joint
- 3. Fit the inner socket firmly over the bolt's spline
- 4. Engage the outer socket of the wrench over the nut
- 5. Pull the trigger. The outer socket will rotate the nut until the torque control groove shears off the spline, thereby achieving proper bolt tension
- 6. Remove the wrench and push the spline ejection trigger to remove the spline from the wrench's socket







- IMPORTANT TIPS ON: Handling Storage Installation
- 1. All structural fasteners should be protected from dirt, moisture and sun light at the job site. No more than the amount of bolts to be used that day should be removed from the container in a protected storage area. Dirty, rusted, or dry bolts should not be used.
- 2. Place all bolts into the connection, with a washer under the nut in standard and short slotted holes. For long slotted and oversize holes, a washer should be placed under the head of the bolt and under the nut. Washer and nut identification markings should always face away from the connection.
- 3. Bring all fasteners in the connection into a snug tight condition, starting from the most ridged part of the connection.

- Staying Out of Trouble at the Job Site
- Tips & Problem Solving Solutions
- Verify Bolt Tension on the Job Site



Staying Out of Trouble at the Job Site

- Review the basic bolt calibrator set up as described for bolt tension calibrator such as a Skidmore Wilhelm.
- 2. Be sure that unit is calibrated and that it is set up with the correct diameter bushings.
- 3. Use hardened spacers for longer bolts, DO NOT stack multiple flat washers.
- 4. Review the instructions for use of the testing device
- 5. Only use bolts from fresh, unopened bolts for testing



Tips & Problem Solving Solutions

- Installation Problems
 - Q: A bolt breaks in the threaded portion before the spline shears off?
 - Answer: Mostly likely the torque co-efficiency value has decreased.



Possible Causes

- 1. Storage conditions allowing moisture, exposure to rain, high humidity, temperatures over 140 degrees
- 2. Lubrication of the product beyond "as delivered" condition from the factory. (Use of oil, grease or wax on the product components at the job site is prohibited.)
- 3. Adhesion of oils, paints, mill scale, dirty burrs or foreign material on the faying surfaces which may allow rotation of the bolt or rotation of the washer with the nut during tightening operation.
- 4. Not properly bringing the connection to the sung tight condition before final wrench tightening which may allow for the bolt to rotate, same as hex bolts.
- 5. Possible misalignment of the connection members that may prevent proper contact of the bolt head and faying surface.
- 6. Exposure to the environment over an extended time period before final tightening.



Tips & Problem Solving Solutions

- Q: Spline breaks at the shear groove before joint connection is made or before specified fastener tension is achieved in bolt tension testing device? Answer: Mostly likely the torque co-efficiency value has become higher. Possible Causes:
- 1. Storage and handling conditions allowing sand, dirt, rust or other foreign material to accumulate on the threads of the bolt or nut.
- 2. Rough handling of the fasteners that would cause nicks or gouges on the bolt and nut.
- 3. Exposure to environmental conditions that cause rust to form on the threads of the bolt nut or washer face.
- 4. Failure to follow AISC procedures for initial tightening in bringing all plies of the joint into firm contact before final tightening. (i.e. trying to draw distorted plies together and shearing the spline before the plies are in contact instead of using "fit up" bolts.) On a TC bolt, the spline will shear off when too great of a torque force is applied. Whereas a hex bolt may be torqued beyond the plastic in the bring without the knowledge of together.

www.dot.state.pa.us

Staying Out of Trouble at the Job Site

- Storage and handling conditions allowing sand, dirt, rust or other foreign material to accumulate on the threads of the bolt or nut.
- 2. Rough handling of the fasteners that would cause nicks or gouges on the bolt and nut.
- 3. Exposure to environmental conditions that cause rust to form on the threads of the bolt nut or washer face.
- 4. Failure to follow AISC procedures for initial tightening in bringing all plies of the joint into firm contact before final tightening. (i.e. trying to draw distorted plies together and shearing the spline before the plies are in contact instead of using "fit up" bolts.) On a TC bolt, the spline will shear off when too great of a torque force is applied. Whereas a new bolt may be torqued beyond the plastic limit of the bolt without the knowledge of together.

Wrench Problems Spline does not eject from socket

- 1. Check inner socket for abrasions or upsets. Remove replace socket.
- 2. Check inner socket for rust, sand, dirt oil or other foreign material caused by poor handling or care in the field. Clean inner socket and replace if necessary.
- 3. Check bolt spline foreign as a result of poor handling in the field.
- 4. Check ejector spring for contamination, clean components if necessary. Replace spring and pin if broken or worn.
- 5. Check sockets for wear and replace if necessary...



Socket does not engage properly with spline or nut

- 1. Check serrations of the socket for wear and replace if necessary.
- 2. Check socket size to be sure it matches the fastener being used.



Tension Control (TC) Bolt

Snug bolt
Tighten to spline break
Verify tension is correct





Principle
Fasteners and tooling
Installation method
Long bolt installation verification
Short bolt installation verification



Twist-Off Bolt Method

Installation method
Snug joint
Use systematic approach


Tighten until twist-off, following manufacturer's instructions



Quality Assurance Program For Bridge Fabrication


• I AM WATCHING YOU

MAKE ME HAPPY






PennDOT's Quality Assurance Program For Bridge Fabrication







Direct Tension Indicator Method












Direct Tension Indicator Method





Direct Tension Indicator Method

